



**1 FLOOR PLAN**  
1/4" = 1'-0"

**KEY NOTES**

1	STYLING CHAIRS	JASMINE JA-60-P/L-4001 STYLING CHAIR BY KAEMARK UPHOLSTERY COLOR: "BLACK"	21	SCREEN WALL W/ WIRE GRID	ALUMINUM SCREEN WALL UNIT WITH SUPERCUTS HEADER AND SILVER GRAPHIC DISPLAY UNIT BY REGIS FIXTURE COMPANY (SEE DETAIL 1/A-300)
2	SHAMPOO CHAIRS	ONASIS O-67/L-4001 SHAMPOO CHAIR BY KAEMARK UPHOLSTERY COLOR: "BLACK"	22	I.T. EQUIPMENT BACKER BOARD	BACKER BOARD FOR NETWORK EQUIPMENT, SEE GENERAL NOTES AND SHEET E-200 FOR MORE INFORMATION
3	4'-0" BENCH	RECEPTION BENCH BY REGIS FIXTURE COMPANY (MAPLE BASE WITH STAINLESS STEEL LEGS AND BLACK NAUGAHIDE CUSHION) SEE DETAIL 3/A-300	23	WAXING SHELF	WAXING SHELF TO BE INSTALLED BY CONTRACTOR (SEE INSTALLATION INSTRUCTIONS) PROVIDED BY REGIS FIXTURE COMPANY
4	6'-0" BENCH	RECEPTION BENCH BY REGIS FIXTURE COMPANY (MAPLE BASE WITH STAINLESS STEEL LEGS AND BLACK NAUGAHIDE CUSHION) SEE DETAIL 3/A-300	24	STYLING STATION	BY REGIS FIXTURE COMPANY. (SEE GENERAL NOTES AND DETAILS 1/A-300, 2/A-300, 3/A-300 & 10/A-300)
5	4'-0" BACK CUSHIONS	WALL MOUNTED SEAT BACK WITH "BLACK" NAUGAHIDE BY REGIS FIXTURE CO. (SEE DETAIL 3/A-300)	25	WALL MOUNTED PHOTO FRAME	43"x46" PHOTO WALL FRAME BY REGIS FIXTURE COMPANY, INSTALLED BY CONTRACTOR. COLOR "BLACK" (SEE DETAIL 3/A-300)
6	6'-0" BACK CUSHIONS	WALL MOUNTED SEAT BACK WITH "BLACK" NAUGAHIDE BY REGIS FIXTURE CO. (SEE DETAIL 3/A-300)	26	WALL MOUNTED PHOTO FRAME	43"x46" PHOTO WALL FRAME BY REGIS FIXTURE COMPANY, INSTALLED BY CONTRACTOR. COLOR "SILVER" (SEE DETAIL 3/A-300)
7	4'-0" BENCH W/ BACK	RECEPTION BENCH W/ ATTACHED BACK REST BY REGIS FIXTURE COMPANY (MAPLE BASE WITH STAINLESS STEEL LEGS AND BLACK NAUGAHIDE CUSHION)	27	WALL MOUNTED COAT RACK	3/4" MAPLE BOARD W/ 6 PEGS BY REGIS FIXTURE COMPANY MOUNTED @ 5'-6" AFF. PROVIDE FIRE RETARDANT BLOCKING AS REQUIRED (SEE DETAIL 13/A-300)
8	MAGAZINE END TABLE	MAGAZINE TABLE BY REGIS FIXTURE COMPANY, GREY LAMINATE - ARBORITE TATAMI NAZUMI F-124, CA FINISH.	28	SHAMPOO SINK	INSTALL ON BULKHEAD FURNISHED BY SUPERCUTS, RUN SMALL BEAD OF CLEAR SILICONE CAULK ACROSS TOP OF BOWL (SEE DETAIL 2/A-300)
9	WASHER/DRYER	PURCHASED LOCALLY BY SUPERCUTS. (SEE DETAIL 5/A-300 AND SHEETS E200 & P100 FOR MORE INFORMATION)	29	EXISTING WATER CLOSET	SEE PLUMBING FIXTURE SCHEDULE ON SHEET P-100 FOR INFORMATION
10	NOT USED		30	EXISTING LAVATORY	SEE PLUMBING FIXTURE SCHEDULE ON SHEET P-100 FOR INFORMATION
11	SHAMPOO BULKHEAD	BY REGIS FIXTURE COMPANY, GREY LAMINATE - ARBORITE TATAMI NAZUMI F-124, CA FINISH. (SEE DETAIL 2/A-300)	31	DISPENSARY SINK	SEE PLUMBING FIXTURE SCHEDULE ON SHEET P-100 FOR INFORMATION
12	45" UPPER CABINETS	BY REGIS FIXTURE COMPANY, GREY LAMINATE - ARBORITE TATAMI NAZUMI F-124, CA FINISH. (SEE DETAILS 2/A-300 & 2/A-301)	32	NOT USED	
13	RECEPTION DESK	ADA COMPLIANT RECEPTION DESK BY REGIS FIXTURE COMPANY. (SEE DETAIL 6/A-300)	33	EXISTING ELECTRICAL PANELS	EXISTING ELECTRICAL PANEL. SEE ELECTRICAL FOR MORE INFORMATION.
14	TOWEL WARMER AND CABINET	TOWEL WARMER AND CABINET W/ FLAP DOOR, GREY LAMINATE - ARBORITE TATAMI NAZUMI F-124, CA FINISH BY REGIS FIXTURE COMPANY.	34	WATER HEATER	SEE PLUMBING FIXTURE SCHEDULE ON SHEET P-100 FOR INFORMATION
15	SUPER SALON MENU BOARD	PURCHASED AND INSTALLED BY TENANT, E.C. TO INSTALL ELECTRICAL CONNECTIONS (SEE DETAIL 1/A-301 AND SHEET E-200 FOR MORE INFO)	35	PORTABLE DRYER	PORTABLE DRYER UNIT FURNISHED BY TENANT.
16	WALL MOUNTED RETAIL DISPLAY SECTION	RETAIL DISPLAY W/ GREY LAMINATE SHELVES - ARBORITE TATAMI NAZUMI F-124, CA FINISH. BY REGIS FIXTURE COMPANY. (SEE DETAIL 1/A-301)	36	KONECTO FLOOR	CONTRACTOR TO INSTALL FRONT TO BACK. (SEE SHEET A-500 FOR MORE INFORMATION)
17	STAFF COUNTER - 6'-0" MANAGERS DESK - 6'-0"	BY REGIS FIXTURE COMPANY, NEVAMAR "AL-2-IT" "EBONY OXIDE" LAMINATE (SEE DETAILS 2/A-300 & 4/A-300)	37	MONITOR BLOCKING	CONTRACTOR TO INSTALL FIRE RETARDANT (32"W x 24"H) BACKING CENTER 18" AFF. AND 16" FROM END OF RETAIL. (SEE DETAIL 1/A-301 FOR MORE INFO.)
18	PERMANENT SHELVING	HIGH BOOKCASE BY REGIS FIXTURE COMPANY, NEVAMAR "S-6-3T" "DOVE GRAY" LAMINATE (SEE DETAIL 1/A-300)			
19	DISPENSARY CABINET	LAMINATE KITCHEN TYPE SINK BASE CABINET. (34" COUNTER TOP HEIGHT) SUPPLIED BY REGIS FIXTURE COMPANY (SEE DETAIL 5/A-300)			
20	DISPENSARY UPPER SHELVING	PREFINISHED OPEN CABINET W/ FOUR (4) 15-1/2" DEEP ADJUSTABLE SHELVES, SUPPLIED BY REGIS FIXTURE COMPANY (SEE DETAIL 5/A-300)			

**GENERAL NOTES**

- \* CONTRACTOR TO NOTIFY REGIS PROJECT MANAGER OF ANY UNFORSEEN ISSUES, REPAIRS OR REPLACEMENTS REQUIRED IN THE FIELD AT THE START OF CONSTRUCTION.
- \* EXISTING STORE FRONT AND DOORS TO REMAIN. TENANT G.C. TO VERIFY CONDITIONS AND REPAIR AS NEEDED.
- \* PROVIDE 2"x6" FIRE RETARDANT BLOCKING IN ALL WALLS WHICH ARE DESIGNATED TO HAVE STYLING STATIONS (SEE DETAIL 8/A-300). CONTRACTOR TO INSTALL W/ MIN. SCREW SPACING OF 6" O.C. AND USE CONSTRUCTION ADHESIVE (SUCH AS FL200) ON ENTIRE SURFACE.
- \* PROVIDE 2"x6" FIRE RETARDANT BLOCKING IN ALL WALLS WHICH ARE DESIGNATED TO HAVE UPPER SHELVING UNITS ABOVE DISPENSARY SINK, STAFF ROOM COUNTER AND MANAGERS DESK (SEE DETAILS 2/A-300, 4/A-300, AND 5/A-300). CONTRACTOR TO INSTALL W/ MIN. SCREW SPACING OF 6" O.C. AND USE CONSTRUCTION GRADE ADHESIVE (SUCH AS FL200) ON ENTIRE SURFACE.
- \* PROVIDE 2"x6" FIRE RETARDANT BLOCKING IN ALL WALLS WHICH ARE DESIGNATED TO HAVE SHAMPOO UPPER CABINETS. CONTRACTOR TO INSTALL W/ MIN. SCREW SPACING OF 6" O.C. AND USE CONSTRUCTION GRADE ADHESIVE (SUCH AS FL200) ON ENTIRE SURFACE (SEE DETAIL 2/A-301).
- \* CONTRACTOR TO FURNISH AND INSTALL 10" ABC FIRE EXTINGUISHER AT LOCATION DESIGNATED BY LOCAL FIRE INSPECTOR. AND OBTAIN TAG/CERTIFICATION BY LOCAL AUTHORITY IF REQUIRED.
- \* TENANT'S GENERAL CONTRACTOR TO SUPPLY AND INSTALL 2" x 2" x 3/4" FLYWOOD BACKER BOARD FOR NETWORK EQUIPMENT, BACKER BOARD TO BE PAINTED TO MATCH WALLS - GLUE AND SCREW INTO STUDS, INSTALL WITH BOTTOM OF BACKER BOARD @ 6'-0" AFF. SEE FLOOR PLAN AND ELECTRICAL PLANS FOR LOCATION.
- \* FIELD VERIFY ALL DIMENSIONS WITH EXISTING BUILDING CONDITIONS.
- \* PATCH ALL DISTURBED SURFACES TO MATCH EXISTING
- \* G.C. TO PROVIDE ADA SIGNAGE PACKAGE AND INSTALL SIGNS AT LOCATIONS AND POSITIONS INDICATED IN PACKAGE OR AS REQUIRED BY LOCAL CODES.
- \* G.C. AND/OR SUB-CONTRACTOR TO INSTALL ALL "KEY NOTE" ITEMS AS LISTED REGARDLESS OF WHO SUPPLIES THE ITEM.

**WALL LEGEND:**

	EXISTING TO REMAIN		INDICATES PAINT COLOR "PT-3" (ACCENT WALL)
	NEW INTERIOR PARTITION		NEW PARTIAL HEIGHT WALL

**WALL TYPES**

		3-5/8" METAL STUDS @ 16" O.C. W/ 5/8" GYF. BD EA. SIDE TO 10'-0" AFF. - BRACE TO EXISTING STRUCTURE AS REQUIRED - SEE DETAIL 6/A-301 FOR ADDITIONAL INFORMATION.
		3-5/8" METAL STUDS @ 16" O.C. W/ 5/8" GYF. BD EACH SIDE TO 3'-3" AFF.
		FURRING CHANNELS AS REQUIRED W/ 5/8" GYF. BD ON ONE SIDE TO 10'-0" AFF. (B.O. ADJACENT CEILING) - BRACE TO EXISTING STRUCTURE AS REQUIRED

**METAL STUD LIMITING HGT.**

STUD SIZE	GA. (MILS)	STUD SPACING	LIMITING HEIGHT	STUD SIZE	GA. (MILS)	STUD SPACING	LIMITING HEIGHT
3-5/8" DRYWALL GRADE	25 (18)	16	12'-5"	3-5/8" DRYWALL GRADE	22 (21)	16	22'-4"
	22 (21)	16	10'-10"		24	16	19'-6"
	20 (30)	24	12'-8"		20	16	23'-11"
3-5/8" STRUCTURAL GRADE	20 (33)	16	15'-6"	3-5/8" STRUCTURAL GRADE	16 (54)	16	21'-11"
	18 (43)	24	13'-6"		24	24	20'-10"
	16 (54)	24	13'-11"		16	16	26'-0"

NOTE: LIMITING HGT. BASED ON INTERIOR CONDITIONS - 5 PSF AT L/240 NON-COMPOSITE CONDITIONS BASED ON 59M/A (STEEL STUD MANUFACTURERS ASSOCIATION)

SEE STUD MANUFACTURER FOR SPECIFIC HGT. LIMITS WITH VARIATIONS REGARDING STEEL AND DRYWALL CONDITIONS

ALEXANDRA MATIS, NCARB  
10755 SANDHILL ROAD  
DALLAS, TEXAS 75238  
214.343.9400

7/12/2016

#81648

SUPERCUTS  
TENANT BUILD-OUT  
JOHN MICHAEL PLAZA  
720 15TH STREET EAST  
TUSCALOOSA, AL 35401

FLOOR PLAN

**SUPERCUTS**

DATE ISSUED  
TENANT REVIEW 04.20.16  
L.L. REVIEW 04.20.16  
FOR PERMIT 04.20.16  
FINAL SET 04.22.16  
LL COMMENTS 07.12.16

DRAWN BY VS  
CHECKED BY AM  
JOB NO. 16190

A-100